8	41.510	Construction of size stone masonty with available stones in cm 1:6	cum	2287.80	Rupees Two Thousand Two Hundred Fifty Seven and Eighty Paise Only
9	18.66	Providing and laying in position plain cement concrete of mix M15 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation,plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	4409.64	Rupees Four Thousand Four Hundred Nine and Sixty Four Paise Only
10	328.00	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	cum	71.39	Rupees Seventy One and Thirty Nine Paise Only
11	148.00	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete.	cum	315.36	Rupees Three Hundred Fifteen and Thirty Six Paise Only
12	76.88	Refixing stone slabs of drains and pointing in CM(1:3)	cum	62.99	Rupees Sixty Two and Ninety Nine Paise Only
13	231.00	Providing and fixing pre cast using 20mm and downsize graded course aggregate stone using clean leveled approved sand including and conveyance of all materials al lead and lift labour charges of machinery etc., complete of 10cm thick a directed by engineer incharge CC 1:1:5:3 (inclusive of cost of steel and fabrication charges) approved quotation rate	sqm	3323.00	Rupees Three Thousand Three Hundred Twenty Three Only
	19.80	23cms thickness slab	sqm	5798.00	Rupees Five Thousand Seven Hundred Ninety Eight Only
14	712.00	Conveying the excavated earth silt debris and over burden earth etc., to a lead of 10 to 15 kms distance by using private vehicle ,include the cost of loading and unloading charges etc., complete	cum	108.64	Rupees One Hundred Eight and Sixty Four Paise Only

DTP Approved

Signature of the Contractor

21/07/13

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ರಾಜರಾಜೇಶ್ವರಿ ನಗರ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿ

Executive Engineer
Rajarajeshwarinagara Division
B.B.M.P